

**ADDENDUM NO. 1
TO THE CONTRACT DOCUMENTS**

H Street Sidewalk and Lincoln Street Waterline

Madras, Oregon

TO: All Plan Holders

DATE: May 19, 2017

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the above mentioned project, bids due June 13, 2017, as fully and completely as if the same were fully set forth therein.

CONTRACT DOCUMENTS

Add the following language to the **ADA RAMP** Special Provision on page 53 of the Special Provisions:

00759.00 Scope - Add the following to the end of this subsection:

This work consists of removing existing concrete sidewalks, curbs, and sidewalk ramps, and constructing new portland cement concrete sidewalk ramps with curbs.

00759.02 Required Submittals - Before the preplacement conference, submit the following:

(a) Working Drawings - Before the preplacement conference, submit six copies of unstamped working drawings according to 00150.35 for all sidewalk ramp work. Include field verification of each ramp location, and all dimensions and grades necessary to demonstrate compliance with the Standard Drawings and Plans. Notify the Engineer of any deficiencies or non-compliance with the Standard Drawings or Plans. The Engineer will provide additional or modified Plans as needed.

(b) Sidewalk Ramp Plan - At least 21 Calendar Days before the sidewalk ramp work is scheduled to begin, submit a plan for accomplishing all phases of the sidewalk ramp work, including the following:

- Surface preparation
- Compliance with working drawings and details submitted under 00759.02
- Compliance with current Standard Drawings and Plans
- Waste handling and disposal
- All other pertinent information

Do not begin any sidewalk ramp work before the plan for completing the work has been approved.

Material ordered or work done before the Engineer reviews and returns the documents will be at the Contractor's risk.

00759.03 Preplacement Conference - Before beginning any sidewalk ramp work, meet with the Contractor's supervisory personnel and quality control manager, any sidewalk ramp subcontractors' supervisory personnel, and the Engineer at a mutually agreed upon time.

If the Contractor's personnel change, or if the Contractor proposes a significant revision to the plan for accomplishing the sidewalk ramp work, the Engineer may require additional preplacement conferences.

00759.22 Smart Level - Slopes will be verified with the use of a 24 inch SmartTool level model 92379, a 6 inch SmartTool level model 92346. The 6 inch level will only be used to measure counter slope when there is a concrete gutter. All other locations will use the 24 inch level to measure slopes.

00759.46 Concrete - Add the following sentence after the first sentence:

Before placing concrete, verify that forms are correctly positioned to produce sidewalk ramps with proper slopes and dimensions to comply with the Standard Drawings and Plans.

00759.50(c) Driveways, Walks, and Surfacing - Add the following paragraph to the end of this subsection:

In addition, finish concrete surfaces of sidewalk ramps to be within the established slopes and dimensions allowed by the Standard Drawings and Plans. Repair or remove and replace sidewalk ramps not meeting the Standard Drawings and Plans at no additional cost to the Agency.

00759.90 Payment

Item (n) includes the additional work required to construct a new sidewalk ramp in a new concrete sidewalk or monolithic curb and sidewalk. Payment for the area of the new sidewalk ramp will be made under the concrete walk or sidewalk pay item. includes installation of truncated domes on a new concrete or asphalt surface.

Add the following paragraph to the end of this subsection:

No separate or additional payment will be made for Sidewalk Ramp Working Drawings, Sidewalk Ramp Plan, Preplacement Conference, concrete form verification, and any necessary repair or removal and replacement of Sidewalk Ramps.

BIDDERS SHALL ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE SPACE PROVIDED IN THE PROPOSAL. BIDS SUBMITTED WITHOUT ACKNOWLEDGEMENT OF THIS ADDENDUM IN THE PROPOSAL WILL BE CONSIDERED IRREGULAR.

Jeff Hurd, P.E.